



Mr and Mrs (name removed),

4/23/2018

Contained herein is my estimate for the installation of a 1,039 foot Double Sided Commercial Shadow-Box 3-Rail Fence. The breakdown is: 567 feet on the north side and 472 feet on the south side.

The top 2 rails will consist of 2x4's and the bottom rail will be comprised of a 2x6.

The existing shadow-box fence will be removed.

Itemized bundle sizes at (name removed) are:

2x4x10 pressure treated (PT) = 208

2x6x10 pressure treated (PT) = 128

1x6x6 Pickets treated = 240

Below are my calculations as to what I will need to complete the task. (approximately)

2x4x10 PT (rails) = 264 actual / 2x4x10 PT (post mounts) = 132 actual total = 396 / I recommend **(2 bundles)**

2x6x10 PT (rails) = 132 actual / I recommend 148 = **(1 bundle plus 20)**

1x6x6 Pickets treated = 2784 actual / I recommend **(13 bundles)**

6x6x10 PT posts **(4)** just in case I discover any posts that are unacceptable

Quikrete 80-lb high-strength concrete mix **(8)** reason: see above

(16,704) Interchange Brand PS06RG 21 Degree Plastic Collated Hot Dip Galvanized Ring Shank Nails, 2" x .113 for the pickets.

5000/box = **(4 Boxes)**

(2,376) Camo Premium Deck Protech Coated 3-1/2inch x 10 screws for the rails. 25lb box/1350 screws = **(2 boxes)**

I will rebuild and reinstall the north gate to a higher standard at no additional cost.

Total labor cost: \$14 per linear foot (double sided) \$14,546.00 – \$4,946.00 (34%) due to 6x6 posts already in place = \$9,600.00

Legal removal of the existing fence to Walton County Landfill in Defuniak Springs: \$2,493.00

Estimate Total: \$12,093.00

If you find this estimate acceptable below is what will facilitate my completing the project in a more timely fashion.

1. The material will be delivered on or before May 4th.
2. I would like to get your permission to relocate my equipment to your property on May 5th and May 6th with work to commence on May 7th.

Wherever you choose to have the materials placed is where I will set up operations.

I will not leave any equipment or materials on your grass overnight.

If the dates above do not fit into your schedule then I welcome you to propose dates that you find acceptable.

All unused wood will be returned to (name removed) and the money refunded.

I work to standard not to time so an accurate forecast as to the time required to finish the project does not exist. I speculate 9 weekdays beginning May 7th and ending May 17th. Assuming I complete the project prior to May 18th I will remove all of my equipment from your property on May 19th and May 20th. In order to safeguard the quality of my product I may need to move into the week of May 21st through May 25th. If this were to happen then all of my equipment will be removed on May 26th and May 27th.

Thank you for considering Freeport Fencing.

We hope to hear from you.

Freeport Fencing